



NOTES:

1. HE LEAK TEST @1 ATM.  $<5 \times 10^{-8}$  CC/S.
2. HYPOT 630 VDC 500 MEGAOHMS MINIMUM 0.01 SECOND MINIMUM PIN TO PIN AND HOUSING.
3. CONTINUITY TEST W/ MATING CONNECTORS  $<0.5$  OHMS.
4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
5. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
6. REF-OPERATING TEMPERATURE: -25 TO 125 °C
7. SHELLS FOR ITEMS 1 & 2, AND HOUSING (ITEM 3) TO HAVE ELECTRICAL CONTINUITY.

7	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE-BASED
6	1	0185	NUT VS26-SS
5	A/R	PAVE-Seal 150	EPOXY BLACK
4	1	-226 VITON	O-RING -226 VITON 75
3	1	1531	HOUSING VS26-SS
2	1	MS27466T21F41S	RCPT 41 #20 999 SERIES I
1	1	MS27467T21F41P	PLUG 41 #20 999 SERIES I
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.  
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE  $\pm 0.5$   
 X.X DECIMAL  $\pm 0.1$  X.XX DECIMAL  $\pm 0.02$  X.XXX DECIMAL  $\pm 0.005$   
 ANGLES  $\pm 1$  DEGREE SURFACE FINISH 128 microinch RMS

**PAVE technology co.**

2751 Thunderhawk Court  
 Dayton, OH 45414-3445  
 U.S.A.  
 tel (937) 890-1100  
 fax (937) 8905165  
 www.pavetechnologyco.com

DESCRIPTION  
 VS26-SS-150-41-20-27466PS

PART NUMBER  
 2735

REVISION LEVEL -

PROJECTION