



NOTES:

1. HE LEAK TEST @1 ATM. $<5 \times 10^{-8}$ CC/S.
2. HYPOT 630 VDC 500 MEGAOHMS MINIMUM 0.01 SECOND MINIMUM PIN TO PIN AND HOUSING.
3. CONTINUITY TEST W/ MATING CONNECTORS <0.5 OHMS.
4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
5. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
6. REF-OPERATING TEMPERATURE: -25 TO 125 °C
7. SHELLS FOR ITEMS 2 & 3, AND HOUSING (ITEM 3) TO HAVE ELECTRICAL CONTINUITY.

7	74	0185	NUT VS26-SS
6	A/R	SUPER O-LUBE	LUBRICANT O-RING SILICONE BASED
5	A/R	PAVE-Seal 150	EPOXY BLACK
4	1	-226 VITON	O-RING -226 VITON 75
3	1	20FD35SN	RCPT 37#22 SOC
2	1	26FD35PN	PLUG 37#22 PIN
1	1	1531	HOUSING VS26-SS
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ± 0.5
 X.X DECIMAL ± 0.1 X.XX DECIMAL ± 0.02 X.XXX DECIMAL ± 0.005
 ANGLES ± 1 DEGREE SURFACE FINISH 128 microinch RMS

PAVE technology co. 2751 Thunderhawk Court
 Dayton, OH 45414-3445
 U.S.A.
 tel (937) 890-1100
 fax (937) 8905165
 www.pavetechnologyco.com

DESCRIPTION
VS26-SS-150-37-22-999PS

PART NUMBER
2744

REVISION LEVEL -
 PROJECTION