



NOTES:

1. HE LEAK TEST @1 ATM. 5×10^{-8} CC/S.
2. HYPOT 630 VDC 500 MEGOHMS MINIMUM 0.01 SECOND MINIMUM PIN TO PIN AND HOUSING.
3. CONTINUITY TEST W/ MATING CONNECTORS <math>< 0.5</math> OHMS.
4. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
5. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
6. REF-OPERATING TEMPERATURE: -25 TO 125 °C
7. SHELLS FOR ITEMS 2 & 3, AND HOUSING (ITEM 1) TO HAVE ELECTRICAL CONTINUITY.

ITEM	QTY	PART NUMBER	DESCRIPTION
6	1	0185	NUT VS26-SS
5	A/R	PAVE-Seal 150	EPOXY BLACK
4	1	-226 VITON	O-RING -226 VITON 75
3	1	MS27467T17F35P	PLUG 55#22D PIN
2	1	MS27466T17F35S	RCPT 55#22D SOC
1	1	1531	HOUSING VS26-SS

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ± 0.5
 X.X DECIMAL ± 0.1 X.XX DECIMAL ± 0.02 X.XXX DECIMAL ± 0.005
 ANGLES ± 1 DEGREE SURFACE FINISH 128 microinch RMS

PAVE technology co. 2751 Thunderhawk Court
 Dayton, OH 45414-3445
 U.S.A.
 tel (937) 890-1100
 fax (937) 8905165
 www.pavetechnologyco.com

DESCRIPTION
VS26-SS-150-55-22-27466PS

PART NUMBER
2745

REVISION LEVEL
A

PROJECTION