



NOTES:

1. HE LEAK TEST @ 1 ATM. $<10^{-7}$ CC/S.
2. OPTICAL CONTINUITY TEST.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. PERCENTAGE OF PARTS TESTED WILL BE 100% (MAY BE A LESSER PERCENTAGE FOR LARGE PRODUCTION QUANTITIES, UNLESS OTHERWISE NOTED OR REQUIRED).
5. VOIDS SMALLER THAN $\phi 0.035$ ARE ACCEPTABLE.
6. REF-OPERATING TEMPERATURE RANGE -40 TO 105 °C.

6	2	WIRE TIE #820	WIRE TIE NYLON NICHIFU
5	1	EXPANDO TUBING	BLACK
4	1	DUPLEX FO	FIBER OPTIC TERMINATED EACH END
3	1	SIMPLEX FO	FIBER OPTIC TERMINATED EACH END
2	A/R	PAVE-Seal 150	EPOXY BLACK
1	1	NW-25FL	HOUSING NW25-SS
ITEM	QTY	PART NUMBER	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ± 0.5
 X.X DECIMAL ± 0.1 X.XX DECIMAL ± 0.02 X.XXX DECIMAL ± 0.005
 ANGLES ± 1 DEGREE SURFACE FINISH 128 microinch RMS

	2751 Thunderhawk Court Dayton, OH 45414-3445 U.S.A. tel (937) 890-1100 fax (937) 8905165 www.pavetechnologyco.com	
	DESCRIPTION NW25-SS-150-3-FO-82-36	
PART NUMBER 2750	REVISION LEVEL A	PROJECTION