



NOTES:

1. HE LEAK TEST @1 ATM. 10×10^{-7} CC/S OR LESS.
2. HYPOT 630 VDC 500 MΩ .01 SEC MINIMUM, WIRE TO WIRE & HOUSING.
3. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
4. ALL PARTS MUST PASS ALL TESTS.
5. FINISH APPLIES TO SPOTFACE FOR O-RING SEAL ONLY.
6. DIMENSIONS ARE INCHES [millimeters].

6	1	-215 VITON	O-RING -215 VITON 75
5	A/R	PAVE-Seal 150	EPOXY BLACK
4	1	0183	NUT VS15-SS
3	4	KT20	CABLE T/C TYPE K 20AWG TEFLON
2	4	RT20	CABLE T/C TYPE RS 20AWG PFA
1	1	0161	HOUSING VS15L-SS
ITEM	QTY	PART#	DESCRIPTION

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES
 ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE +/-0.5
 .X DECIMAL +/- 0.1 .XX DECIMAL +/- 0.02 .XXX DECIMAL +/-0.005
 ANGLES +/- 1 DEG SURFACE FINISH 128 microinch RMS

2751 Thunderhawk Court
Dayton, Ohio 45414-3445
U.S.A.
(937)890-1100
fax (937)890-5165
www.pavetechnologyco.com

PAVE technology co.

DESCRIPTION
VS15L-SS-150-4p/4p-KT20/RT20-12-48

PART NUMBER
3513

REVISION LEVEL
-

PROJECTION