

- 1. HE LEAK TEST @ 1 ATM 1X10^-7 CC/SEC OR LESS. LEAK TEST PERFORMED WITH A 2-032 VITON O-RING, A GREEN PAINT DOT INDICATES THE PART HAS PASSED THE TEST.
- 2. ALL TESTS ARE PERFORMED AT ROOM TEMPERATURE.
- 3. ALL PARTS MUST PASS ALL TESTS.
- 5. REF-OPERATING TEMPERATURE -20°C TO 125°C.
- 6. REF-PARTS ARE DEFLASHED ON PARTING LINE +0.005 [0.13] MAXIMUM.
- 7. DIMENSIONS ARE INCHES [millimeters].

| 2    | 1   | SCF16666201DA | FLEX CABLE  | PAVE leding                             | 2751 Thunderhawk Court<br>Dayton, OH 45414-3445<br>U.S.A.<br>tel (937) 890-1100 |   |
|------|-----|---------------|-------------|---|---|---|
| 1    | A/R | PAVE-Seal 150 | EPOXY BLACK | p                                       | 71937-1 496<br>21937-1 496  | fax (937) 8905165<br>www.pavetechnologyco.com |
| ITEM | QTY | PART NUMBER   | DESCRIPTION | DESCRIPTION SP47.2/7.2-E-150-1-FLEX-1-1 |   |   |
|      |     |               |             | 01 17.27 7.2 E 100 1 1 EEX 1 1          |   |   |
|      |     |               |             | PART NUMBER MATERIAL NOTED              |   |   |
|      |     |               |             | 4647                                    | REVISION B  | PROJECTION (C)                                |

ALL DIMENSIONS AND TOLERANCES APPLY TO FINISHED PART IN INCHES.
ALLOWABLE TOLERANCES UNLESS SPECIFIED OTHERWISE: NONE ±0.5
X.X DECIMAL ±0.1 X.XX DECIMAL ±0.02 X.XXX DECIMAL ±0.005
ANCIES +1 DEGREE SURFACE FINISH 128 microineh MMS