



**NOTES:**

1. SEE INSTRUCTIONS FOR WIRE COLOR AND WIRE LOCATION.
2. ALL EXITING WIRES TO BE LABELED PER CUSTOMER CALLOUTS, SEE INSTRUCTIONS.
3. He LEAKTEST: <1x10-6 @ 1 ATM, MUST INCLUDE FLANGE ASSEMBLY, TEST EPOXY HOUSING SEPERATELY.
4. FEEDTHRU REQUIRES (1) SPIROLOX RETAINING RING (UR-331), AND (2) -041 VITON O-RINGS.
5. TWISTED PAIR WIRE TO REMAIN TWISTED THROUGH FEEDTHRU.
6. ELECTRICAL CONTINUITY TEST: ALL WIRES PIN TO SOCKET, 1 OHM MAX.
7. ELECTRICAL CONTINUITY TEST: DRAIN DRAIN WIRES PIN TO CRIMP LUG, 1 OHM MAX.
8. HYPOT TEST: 600VDC, 500 Mohms MIN, EACH CABLE ASSY AND ALL CABLES.

**Design Library**



TITLE OR PAVE ORDER CODE  
0531-SS-80-266TP-TE24-18T-360T

PART NUMBER  
0530

